

# KERALA STATE CO-OPERATIVE FEDERATION FOR FISHERIES DEVELOPMENT LTD (MATSYAFED)

Last Date: 24/01/2009 3:00 PM

EMD: 2.5% of the Total Quoted Amount

## TENDER SCHEDULE

**Name of Work: Supply and Installation of refrigeration units for newly constructed Sashmi Tuna Project at Ice and Freezing Plant, Kochi**

Sl. No.	Qty	Description	Unit	Rate		Amount
				In Figures	In Words	
1	2 Nos.	Supply, Installation, Testing and Commissioning of refrigeration unit for Sashmi Store of size 9 x 9 x 2.5m, Each units 4 tones capacity air temperature -2° EUROVENT certified evaporators should be ceiling mounted with electrical defrosting. Aluminium powder coated inner grooved copper tubing with floating technology, Silent fans with external rotor motor, evaporators should be sleek type with high efficiency heat transfer. Condensing units with semihermetic compressors, Air cooled condenser with all necessary refrigeration and electrical controllers compressors and condensing unit make should be unique refrigerant - R22 microprocessor based control panels should be provided including all cost and labour etc complete as directed by the officers of Matsyafed	Each			

2	2 Nos	Supply, Installation testing and Commissioning of refrigeration unit for chill room of size 8.70x7.75x2.50m each units 4 ton capacity air temperature -2° EUROVENT certified evaporators should be ceiling mounted with electrical defrosting. Aluminium powder coated inner grooved copper tubing with floating technology, Silent fans with external rotor motor, evaporators should be sleek type with high efficiency heat transfer. Condensing units with semihermetic compressors, Air cooled condenser with all necessary refrigeration and electrical controllers compressors and condensing unit make should be unique refrigerant - R22 microprocessor based control panels should be provided including all cost and labour etc complete as directed by the officers of Matsyafed	Each			
3	9 Nos.	Supply, installation, testing and commissioning of split type Air conditioning unit including stabilizers for pre-processing hall, processing hall, packing section. Each units 1.5 tones capacity, air temperature +22° specifications, including all cost and labour etc complete as directed by the officers of Matsyafed	Each			
<b>TOTAL</b>						

NB: Company to quot the rates both figures and words

**Signature with Name and Address  
of Company**

**Deputy General Manager  
(Engineering)**